Container studios: 2 identical farm-stay guest units

IKEA-style flat-pack fit-out of standard 20 ft containers · materials and fabrication in Kigali

Net interior 5798 x 2252 x 2316 mm (13.1 m2) · Layout B (D-020)
MALM-style bed up to 1,600 x 2,000 with two storage boxes, bedside table and lamp · sofa, low table, two chairs
Galley 1600 mm on the bathroom wall: fridge, induction, sink; 30 L heater over the WC
Bathroom 1150 x 2252 mm · shower tray 1000 x 900
Max demand about 30 A per unit (heater + AC shed while the hob runs) · 32 A inlet
Shared septic 3.5 m3, 2 chambers 2:1 · storage tank 2.5 m3
Roof terrace on the corner castings, open guardrail · tinted polycarbonate canopy over the front deck

Status: PRELIMINARY. Opening positions are photo estimates (+/-150 mm, AS-14).
Nothing is cut until study/studio/survey.csv is complete and the set is re-issued.
Structural items (roof terrace, deck canopy, stair) need an engineer's sign-off before guest use.
Electrical ratings are design intent until a RURA class A electrician designs and certifies.

No.	Title
A-001	Cover and drawing index
A-101	Existing condition (photo-scaled)
A-102	Layout options considered
A-103	Furniture and dimension plan
A-201	Interior elevations: back wall and front wall
A-202	End elevations and cross-section
A-401	Build-up details
S-101	Roof terrace, deck canopy and stair: plan and elevation
E-101	Electrical layout plan
E-201	Single-line diagram: inlet and unit board
E-202	Circuit schedule, earthing and bonding
P-101	Plumbing layout plan (supply and drainage)
P-201	Pipework isometric (unit)
P-301	Site water and sanitation schematic
J-101	Kit K1: Insulation and lining (exploded)
J-102	Kit K2: Bathroom (exploded)
J-103	Kit K3: Kitchen (exploded)
J-104	Kit K4: Bed (exploded)
J-105	Kit K5: Bedside table (exploded)
J-106	Kit K6: Sofa, table and chairs (exploded)
J-107	Kit K7: Trims (exploded)
J-108	Kit K11: Roof terrace (exploded)
C-101	Cutting diagrams (panel saw: rip strips, then crosscut)
C-102	Cutting diagrams (panel saw: rip strips, then crosscut)
C-103	Cutting diagrams (panel saw: rip strips, then crosscut)
C-104	Cutting diagrams (panel saw: rip strips, then crosscut)
C-105	Cutting diagrams (panel saw: rip strips, then crosscut)
C-106	Cutting diagrams (panel saw: rip strips, then crosscut)
C-107	Cutting diagrams (panel saw: rip strips, then crosscut)

PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Cover and drawing index — **A-001**

Scale NTS · Rev A2 · 2026-10-28 · mm — **PRELIMINARY**

PLAN (roof removed)




Existing (photo 2026-10-25, not published):
- standard 20 ft container on a raised steel deck, deck about 700 above ground, steps at end B
- sliding glass wall, white frames, about 3.0 x 2.25 m
- narrow hinged steel door near end B (about 0.55 m)
- yellow unit: original cargo doors at end B
- one corner casting rests on a rock: level first
- temporary wiring; timber lining in one unit

Positions are scaled from the 6,058 mm length [E]. Survey every unit before cutting (studio-site page).

Structure: the glazed side is about 60 % open and no longer braces the box (STU-03). Do not cut the back or end walls; holes there max 152 mm each.

FRONT ELEVATION (from the deck; end A on the left, as in the photo)



PRELIMINARY


Farm container studios	farm.databayt.org/docs/studio
Existing condition (photo-scaled)	**A-101**
Scale 1:30 · Rev A2 · 2026-10-28 · mm	PRELIMINARY

B (chosen, D-020): galley on the bathroom wall




PASS: a real living room; one wet core; robust to +/-150 mm

A (D-015, replaced): kitchen on the back wall



Passes the rules, but the living room is only a table by the glass

C: keep the narrow door as an entrance




FAIL: WC side 364 < 400, front 500 < 600; 550 mm door

Options checked by the generator against the same rules (scripts/studio/validate.py):
WC centreline at least 400 from walls and 600 clear in front; shower tray at least 1,000 x 900; galley aisle at least 800 to the sofa; door and drawer sweeps clear of solids; partition on the solid strip after the glazing.
Layout B keeps A's bathroom (WC facing across the width) and passes at the estimate and at -150 / +150 mm.
A first version with the WC facing along the container failed if the glazing ended more than about 70 mm later.
Precedents: Cleveland 20 ft (STU-46), Falcon (STU-47), Pod-Tainer (STU-48), container hotels (STU-49, STU-50).

PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Layout options considered	**A-102**
Scale 1:50 · Rev A2 · 2026-10-28 · mm	**PRELIMINARY**



PRELIMINARY


Check	Rule	Result	Value
KO-WC	WC front clearance 600	pass	
KO-SHOWER	Shower entry 600	pass	
KO-BASIN	Standing space at the basin	pass	
KO-BDOOR	Door swing into the bathroom (hinged by the partition)	pass	
KO-KITCHEN	Galley aisle 650 (worktop to the sofa)	pass	
KO-DRAWERS	Storage boxes pull out 600	pass	
R-TRAY	Shower tray length (mm)	pass	1000 >= 1000
R-WC-SIDE	WC centreline to the shower (mm)	pass	400 >= 400
R-WC-SIDE2	WC centreline to the bathroom wall (mm)	pass	400 >= 400
R-WC-FRONT	Clear space in front of the WC (mm)	pass	600 >= 600
R-BDOOR	Bathroom door clear opening (mm)	pass	600 >= 600
R-AISLE	Walkway, worktop to the sofa end (mm)	pass	658 >= 650
R-BEDSIDE	Sofa clear of the bedside table (mm)	pass	20 >= 20
R-GALLEY	Galley clear of the bathroom wall end (mm)	pass	100 >= 30
R-PASS	Walk past the galley end to the wash lobby (mm)	pass	652 >= 600
R-BED	Room beside the bed foot (mm)	pass	214 >= 50
R-HEIGHT	Clear height (mm)	pass	2316 >= 2250
R-PART	Partition clear of the old door (mm)	pass	342 >= 150

Farm container studios — farm.databayt.org/docs/studio


Furniture and dimension plan — **A-103**

Scale 1:25 · Rev A2 · 2026-10-28 · mm — **PRELIMINARY**

BACK WALL (looking at y = 0)




FRONT WALL (looking at the glass from inside; end B on the left)




PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Interior elevations: back wall and front wall	**A-201**
Scale 1:30 · Rev A2 · 2026-10-28 · mm	**PRELIMINARY**


END A (bed) looking at x = 0



GALLEY looking at the bathroom wall



END B (bathroom) looking at x = L




Clear height about 2,323 mm after a 60 mm ceiling and a 10 mm floor build-up (AS-15).
The 2012 rules asked 2.4 m over half a habitable room (STU-11, superseded); the founder reports approval.
Wall fans, not ceiling fans (blades would be below 2.1 m). Split-AC provision: sleeve + 16 A circuit.

PRELIMINARY


Farm container studios	farm.databayt.org/docs/studio
End elevations and cross-section	**A-202**
Scale 1:25 · Rev A2 · 2026-10-28 · mm	**PRELIMINARY**

WALL (steel to room)




steel sheet | air gap | 12 mm plywood | 38 mm timber frame | 12 mm plywood | PU foam 38 | 12 mm plywood | 38 mm timber frame | 12 mm plywood | paint finish

CEILING (roof to room)




spray foam 238 | 12 mm plywood | 38 mm timber frame | 12 mm plywood | spray foam 238

BATHROOM WET WALL




stud 38 | cement board 12 | vinyl sheet 2 | cement board 12

PARTITION 70 (living | bath)



marine ply 18 | timber stud | wood wool board 12

FLOOR (living)



container plywood 28 | PE membrane 0.25


W1 (old door): 2 mm steel infill welded, foamed with the walls, up to 1,150; obscure louvre window above with insect mesh; the bathroom fan exits through the infill panel (no new hole in a bracing wall).

Floor: never sand the treated plywood (STU-07); membrane, then 12 mm sheets. Drains pass between cross-members, never through them.
Steel faces: rust converter + zinc primer before foam.
Closed-cell spray foam, no gaps: no air path to the steel. No welding after foam.


PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Build-up details	**A-401**
Scale 1:5 · Rev A2 · 2026-10-28 · mm	PRELIMINARY

PLAN (deck canopy omitted)



FRONT ELEVATION



Element	Specification
Deck beams	RHS 150x100x5, 2 no., bear on the 4 corner castings only
Joists	RHS 80x40x3 at 600
Deck	hardwood boards 140 x 25, 5 mm gaps
Guardrail	1,100 high, SHS posts at 1.5 m, hardwood top rail
Infill	4 mm stainless cables at 90 mm (gaps under 100)
Roof	open to the sky: no canopy over the terrace (D-020)
Veranda canopy	polycarbonate on own posts + ledger over the front deck
Stair	dog-leg, 16 risers about 175, goings 250, 850 wide, handrails
Loads [A]	3.0 kN/m2 live, 0.74 kN/m rail, wind uplift: engineer to sign


The glazed side does not brace the box: nothing bears on the slider head or the open side's top rail (STU-03).
All steelwork bonded to the earth electrode (lightning).
Polycarbonate not found online in Kigali: fallback translucent GRP or opal corrugated sheet (Tolirwa / Safintra, field check).
Engineer's inspection before any guest uses the roof (R26).

PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Roof terrace, deck canopy and stair: plan and elevation **S-101**

Scale 1:50 · Rev A2 · 2026-10-28 · mm **PRELIMINARY**



Mounting heights z above the finished floor (mm).
Bathroom: light IP65, extract IPX4 (zone 1), no sockets, switches outside the door.
Cables in 20 mm conduit in the lining: up into the ceiling void, along it, then vertical drops to each device; grommets at every steel penetration.
C6 (deck, stair, roof lights) runs outside in UV-stable conduit; outdoor points IP65/66 on the bonded steelwork.

L10/C6 L10/C6

Pt	Cct	Description	z
DB		Unit board, 24 modules (2 x 12), by the galley	1625
PI		Power inlet 32 A IP67 (IEC 60309 blue, 2P+E),	1225
L1	C1	Ceiling light, bed	2316
L2	C1	Ceiling light, living	2316
L3	C1	Ceiling light, galley	2316
L4	C1	Bathroom light IP65	2316
L5	C1	Wall reading light over the bed (wall side)	1150
L7	C1	Under-cabinet LED strip	1790
S1	C1	Entry: bed (2-way), living and galley lights	1100
S2	C1	Bed: ceiling light (2-way), over the bedside t	1000
S3	C1	Bathroom light + fan (outside)	1100
F1	C1	Bathroom extract 100 mm, IPX4 for zone 1, with	2100
F2	C1	Wall fan 300 mm	2050
P1	C2	Socket + USB-C in the headboard (wall side)	750
P2	C2	Bedside socket + USB-C (reading lamp)	650
P3	C2	Socket + USB-C over the sofa arm, for the sofa	850
P5	C2	Deck socket IP66, outside by the slider	400

Pt	Cct	Description	z
P6	C3	Worktop double socket 1	1100
P7	C3	Worktop double socket 2 (back wall)	1100
P8	C3	Fridge socket	250
P12	C3	Double socket above the hood: hood + Wi-Fi rou	1720
P9	C4	Hob outlet plate, isolated at its RCBO on the	600
P10	C5	Heater DP switch + timer	1700
L8	C6	Deck light IP65, under the veranda canopy	1984
S5	C6	Deck light, beside the entry switch	1100
S4	C6	Stair and roof lights (2-way), IP65 at the sta	1100
L10	C6	Stair light IP65	1500
S6	C6	Stair and roof lights (2-way), IP65 at the sta	3579
L9	C6	Roof terrace lights IP65 (x2), under the front	3579
P11	C7	AC provision: isolator	2150
AL1		Smoke alarm, 10-year battery	2316
AL2		Heat alarm, kitchen, 10-year battery	2316
E1		Earth rod 1.5 m copper-bonded in an inspection	-700


PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Electrical layout plan — **E-101**

Scale 1:25 · Rev A2 · 2026-10-28 · mm — **PRELIMINARY**

ONE STUDIO, FROM ITS INLET TO EVERY CIRCUIT



The studio plugs in: any 230 V source protected at 32 A or less; the 32 A main breaker protects the inlet and tails whatever feeds them.
Priority relay on C4: while the hob runs, contactor K sheds C5 and C7 (heater and AC).
Diversified maximum demand about 30 A (AS-19), within the 32 A inlet. One RCBO 30 mA type A per circuit.
TT earthing: the studio's own earth rod at the board; never rely on the supply's earth (STU-37).
Ratings are design intent: a RURA class A electrician designs and certifies (STU-15), to RS 565-1:2011 (STU-14).

PRELIMINARY


Farm container studios	farm.databayt.org/docs/studio
Single-line diagram: inlet and unit board	**E-201**
Scale NTS · Rev A2 · 2026-10-28 · mm	**PRELIMINARY**

CIRCUIT SCHEDULE (Ib design current, Iz derated capacity, drop at the far point)

Cct	Serves	Device	mm2	Ib A	Iz A	Run m	Drop %
C1	Indoor lights and fans	B6	1.5	0.6	13.6	34.9	0.25
C2	Sockets: bed, sofa and deck	B16	2.5	8.0	18.3	24.3	1.52
C3	Kitchen sockets, fridge and hood	B16	2.5	14.0	18.3	12.3	1.35
C4	Induction hob	B20	4	15.2	24.4	4.4	0.32
C5	30 L water heater	B16	2.5	8.7	18.3	3.9	0.27
C6	Outdoor lights: deck, stair and roof	B6	1.5	0.2	13.6	16.5	0.03
C7	AC provision	B16	2.5	12.0	18.3	3.9	0.37
C8	Spare	B16	2.5	-	-	-	-

Maximum demand item	A
lighting	0.3
fans	0.3
sockets	16.4
hob	11.6
heater	8.7
ac	4.3
total_A	30.0

EARTHING AND BONDING (TT)




Bonding: finely stranded green-yellow (16 mm2 [A]) from each steel item to the MET. RA x 30 mA must stay under 50 V; aim much lower for lightning (measure on site). Tests before handover: continuity, insulation resistance, polarity, earth electrode resistance, RCD trip time, SPD status; certificate from the licensed electrician. Bathroom: zone 1 above the tray to 2.25 m (IPX4); 30 mA on every circuit (STU-38).

PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Circuit schedule, earthing and bonding — **E-202**

Scale NTS · Rev A2 · 2026-10-28 · mm — **PRELIMINARY**



Run	System	Size	m	Fall	Note
D1	soil	DN110	1.8	1:38	WC to IC1, 1:40
D2	waste	DN50	1.3	1:34	Shower (90 mm tray waste) joins the soil run
D3	waste	DN40	2.1	1:28	Basin (wash lobby) joins the soil run
D4	waste	DN50	3.3	1:26	Kitchen sink to the grease trap (separate so
V1	vent	DN75	6.7	-	Open vent up end B to 900 above the guardrai
W1	cold	DN25	2.9	-	Cold main in from the farm, up into the sink
W2	cold	DN20	1.8	-	Cold up end wall B to the heater
W3	cold	DN20	0.1	-	Cold to the sink's angle valve
W4	cold	DN20	5.0	-	Cold through the partition and the walls to
W5	cold	DN20	1.0	-	Cold on to the basin
W6	cold	DN20	0.1	-	Cold to the mixing valve
H1	hot	DN20	2.4	-	Hot (60 C) from the heater down to the mixin
H2	hot	DN20	3.9	-	Hot back along the walls to the sink (direct
T1	tempered	DN20	1.2	-	TMV 41-44 C up to the shower valve
T2	tempered	DN20	1.2	-	Tempered to basin


PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Plumbing layout plan (supply and drainage) — **P-101**


Scale 1:25 · Rev A2 · 2026-10-28 · mm — **PRELIMINARY**

Supply: PPR PN20, 20/25 mm. Hot leaves the 30 L heater at 60 C; a thermostatic mixer (TMV) delivers 41-44 C to the shower and basin; the kitchen sink gets direct hot (labelled).
Drainage hangs in the void under the raised floor (the container is about 700 mm up), between cross-members: WC 110, shower and sink 50, basin 40, falls at least 1:40.
Vent: 75 mm open vent up end B to 900 above the guardrail line (or an AAV inside).
Kitchen sink waste runs separately to a grease trap and its own soak pit (STU-11).



PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Pipework isometric (unit)	**P-201**
Scale NTS · Rev A2 · 2026-10-28 · mm	**PRELIMINARY**




Septic sizing, P = 8	m3
DRS 143 draft (STU-10)	3.0
2012 regulations (STU-11)	2.72
180P + 2,000 L (STU-09 style)	3.08
Design (largest, rounded)	3.5

Siting rules (check on the site plan):
- at least 50 m from the borehole and any well (2012 rules; DRS 143 draft: soak pit 18 m)
- at least 50 m from the lake (LOC-01, LOC-02)
- at least 3-7 m from buildings and the boundary
- downhill of the borehole; tanker within 30 m
- soak pit only where groundwater is more than 2.5 m down and percolation is 25-125 mm/h


No guests until the system passes inspection.

DRAINAGE



PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Site water and sanitation schematic	P-301
Scale NTS · Rev A2 · 2026-10-28 · mm	PRELIMINARY




Part	Name	Mat.	L x W x T
K1-01	Back wall lining	PLY12	2316 x 1144 x 12
K1-02	Back wall lining	PLY12	2316 x 1144 x 12
K1-03	Back wall lining	PLY12	2316 x 1144 x 12
K1-04	Back wall lining	PLY12	2316 x 1144 x 12
K1-05	End A lining	PLY12	2316 x 1126 x 12
K1-06	End A lining	PLY12	2316 x 1126 x 12
K1-07	Front wall lining (end A)	PLY12	2316 x 690 x 12
K1-08	Front wall lining (end A)	PLY12	2316 x 690 x 12
K1-09	Front head strip	PLY12	1500 x 76 x 12
K1-10	Front head strip	PLY12	1500 x 76 x 12
K1-11	Ceiling panel	PLY12	2252 x 1160 x 12
K1-12	Ceiling panel	PLY12	2252 x 1160 x 12
K1-13	Ceiling panel	PLY12	2252 x 1160 x 12
K1-14	Ceiling panel	PLY12	2252 x 1160 x 12
K1-15	Ceiling panel	PLY12	2252 x 1160 x 12

PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Kit K1: Insulation and lining (exploded) **J-101**

Scale NTS · Rev A2 · 2026-10-28 · mm **PRELIMINARY**




Part	Name	Mat.	L x W x T
K2-01	Partition skin (galley face)	MPLY18	2316 x 885 x 18
K2-02	Partition skin (galley face)	MPLY18	2316 x 885 x 18
K2-03	Cross wall skin over the door	MPLY18	600 x 266 x 18
K2-04	Cross wall skin (lobby face)	MPLY18	2316 x 550 x 18
K2-05	Door jamb (hinge side)	MPLY18	2050 x 52 x 18
K2-06	Door jamb (latch side)	MPLY18	2050 x 52 x 18
K2-07	Door head	MPLY18	564 x 52 x 18
K2-08	Mirror cabinet side 1	MPLY18	650 x 108 x 18
K2-09	Mirror cabinet side 2	MPLY18	650 x 108 x 18
K2-10	Mirror cabinet top	MPLY18	364 x 108 x 18
K2-11	Mirror cabinet bottom	MPLY18	364 x 108 x 18
K2-12	Mirror cabinet shelf	MPLY18	362 x 98 x 18
K2-13	Mirror cabinet door	MPLY18	650 x 400 x 18

PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Kit K2: Bathroom (exploded) **J-102**

Scale NTS · Rev A2 · 2026-10-28 · mm **PRELIMINARY**




Part	Name	Mat.	L x W x T
K3-01	Fridge bay side	PLY18	762 x 588 x 18
K3-02	Fridge bay top rail	PLY18	532 x 100 x 18
K3-03	Fridge bay back rail	PLY18	532 x 100 x 18
K3-H-01	Hob base side L	PLY18	762 x 588 x 18
K3-H-02	Hob base side R	PLY18	762 x 588 x 18
K3-H-03	Hob base bottom	PLY18	588 x 564 x 18
K3-H-04	Hob base front rail	PLY18	564 x 100 x 18
K3-H-05	Hob base back rail	PLY18	564 x 100 x 18
K3-H-06	Hob base back	PLY12	762 x 600 x 12
K3-H-07	Hob base drawer front 1	PLY18	597 x 378 x 18
K3-H-08	Hob base drawer side L 1	PLY12	566 x 160 x 12
K3-H-09	Hob base drawer side R 1	PLY12	566 x 160 x 12
K3-H-10	Hob base drawer back 1	PLY12	514 x 160 x 12
K3-H-11	Hob base drawer bottom 1	PLY12	554 x 514 x 12
K3-H-12	Hob base drawer front 2	PLY18	597 x 378 x 18
K3-H-13	Hob base drawer side L 2	PLY12	566 x 160 x 12
K3-H-14	Hob base drawer side R 2	PLY12	566 x 160 x 12
K3-H-15	Hob base drawer back 2	PLY12	514 x 160 x 12
K3-H-16	Hob base drawer bottom 2	PLY12	554 x 514 x 12
K3-S-01	Sink base side L	PLY18	762 x 588 x 18
K3-S-02	Sink base side R	PLY18	762 x 588 x 18
K3-S-03	Sink base bottom	PLY18	588 x 414 x 18
K3-S-04	Sink base front rail	PLY18	414 x 100 x 18
K3-S-05	Sink base back rail	PLY18	414 x 100 x 18
K3-S-06	Sink base back	PLY12	762 x 450 x 12
K3-S-07	Sink base door 1	PLY18	758 x 447 x 18
K3-T-01	Overhead cabinet side L	PLY18	500 x 488 x 18
K3-T-02	Overhead cabinet side R	PLY18	500 x 488 x 18
K3-T-03	Overhead cabinet bottom	PLY18	1564 x 488 x 18
K3-T-04	Overhead cabinet top	PLY18	1564 x 488 x 18
K3-T-05	Overhead cabinet back	PLY12	1600 x 500 x 12
K3-T-06	Overhead cabinet door 1	PLY18	797 x 496 x 18
K3-T-07	Overhead cabinet door 2	PLY18	797 x 496 x 18
K3-WT	Worktop 38 mm	WTOP38	1600 x 620 x 38
K3-HS	Hood shelf	PLY18	600 x 480 x 18
K3-PL	Plinth	PLY18	1050 x 98 x 18

PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Kit K3: Kitchen (exploded) — **J-103**

Scale NTS · Rev A2 · 2026-10-28 · mm — **PRELIMINARY**



Part	Name	Mat.	L x W x T
K4-01	Headboard (full height, on the bac	PLY18	1640 x 1000 x 18
K4-02	Rail, end-A side	PLY18	2020 x 432 x 18
K4-03	Rail, room side (top)	PLY18	2020 x 80 x 18
K4-04	Rail, room side (plinth)	PLY18	2020 x 60 x 18
K4-05	Rail, head	PLY18	1604 x 432 x 18
K4-06	Rail, foot	PLY18	1604 x 432 x 18
K4-07	Spine	PLY18	1984 x 432 x 18
K4-08	Slat ledger, end-A side	PLY18	1984 x 60 x 18
K4-09	Slat ledger, room side	PLY18	1984 x 60 x 18
K4-10	Deck slat 1	PLY18	1604 x 90 x 18
K4-11	Deck slat 2	PLY18	1604 x 90 x 18
K4-12	Deck slat 3	PLY18	1604 x 90 x 18
K4-13	Deck slat 4	PLY18	1604 x 90 x 18
K4-14	Deck slat 5	PLY18	1604 x 90 x 18
K4-15	Deck slat 6	PLY18	1604 x 90 x 18
K4-16	Deck slat 7	PLY18	1604 x 90 x 18
K4-17	Deck slat 8	PLY18	1604 x 90 x 18
K4-18	Deck slat 9	PLY18	1604 x 90 x 18
K4-19	Deck slat 10	PLY18	1604 x 90 x 18
K4-20	Deck slat 11	PLY18	1604 x 90 x 18
K4-21	Deck slat 12	PLY18	1604 x 90 x 18
K4-22	Deck slat 13	PLY18	1604 x 90 x 18
K4-23	Deck slat 14	PLY18	1604 x 90 x 18
K4-24	Deck slat 15	PLY18	1604 x 90 x 18
K4-25	Deck slat 16	PLY18	1604 x 90 x 18
K4-26	Deck slat 17	PLY18	1604 x 90 x 18
K4-27	Deck slat 18	PLY18	1604 x 90 x 18
K4-28	Deck slat 19	PLY18	1604 x 90 x 18
K4-29	Deck slat 20	PLY18	1604 x 90 x 18
K4-30	Side panel, head end	PLY18	754 x 292 x 18
K4-31	Drawer divider	PLY18	682 x 352 x 18
K4-32	Storage box 1 front	PLY18	602 x 288 x 18
K4-33	Storage box 1 side 1	PLY12	600 x 230 x 12
K4-34	Storage box 1 side 2	PLY12	600 x 230 x 12
K4-35	Storage box 1 back	PLY12	562 x 230 x 12
K4-36	Storage box 1 bottom	PLY12	588 x 562 x 12
K4-37	Storage box 2 front	PLY18	602 x 288 x 18
K4-38	Storage box 2 side 1	PLY12	600 x 230 x 12
K4-39	Storage box 2 side 2	PLY12	600 x 230 x 12
K4-40	Storage box 2 back	PLY12	562 x 230 x 12
K4-41	Storage box 2 bottom	PLY12	588 x 562 x 12


PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Kit K4: Bed (exploded) — **J-104**

Scale NTS · Rev A2 · 2026-10-28 · mm — **PRELIMINARY**

Part	Name	Mat.	L x W x T
K5-01	Table top	PLY18	340 x 340 x 18
K5-02	Leg strip (two make a 36 x 36 leg)	PLY18	532 x 36 x 18
K5-03	Leg strip (two make a 36 x 36 leg)	PLY18	532 x 36 x 18
K5-04	Leg strip (two make a 36 x 36 leg)	PLY18	532 x 36 x 18
K5-05	Leg strip (two make a 36 x 36 leg)	PLY18	532 x 36 x 18
K5-06	Leg strip (two make a 36 x 36 leg)	PLY18	532 x 36 x 18
K5-07	Leg strip (two make a 36 x 36 leg)	PLY18	532 x 36 x 18
K5-08	Leg strip (two make a 36 x 36 leg)	PLY18	532 x 36 x 18
K5-09	Leg strip (two make a 36 x 36 leg)	PLY18	532 x 36 x 18
K5-10	Lower shelf	PLY18	268 x 268 x 18




PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Kit K5: Bedside table (exploded) — **J-105**

Scale NTS · Rev A2 · 2026-10-28 · mm — **PRELIMINARY**



Part	Name	Mat.	L x W x T
K6-01	Table top 860 x 500	PLY18	860 x 500 x 18
K6-02	Table leg A (cross-halving slot)	PLY18	740 x 532 x 18
K6-03	Table leg B (cross-halving slot)	PLY18	532 x 400 x 18
K6-04	Chair 1 seat	PLY18	400 x 400 x 18
K6-05	Chair 1 leg A	PLY18	382 x 360 x 18
K6-06	Chair 1 leg B	PLY18	382 x 342 x 18
K6-07	Chair 1 back	PLY18	800 x 400 x 18
K6-08	Chair 2 seat	PLY18	400 x 400 x 18
K6-09	Chair 2 leg A	PLY18	382 x 360 x 18
K6-10	Chair 2 leg B	PLY18	382 x 342 x 18
K6-11	Chair 2 back	PLY18	800 x 400 x 18


PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Kit K6: Sofa, table and chairs (exploded) **J-106**

Scale NTS · Rev A2 · 2026-10-28 · mm **PRELIMINARY**

Part	Name	Mat.	L x W x T
K7-03	Skirting, front strip	PLY12	1368 x 70 x 12
K7-04	Slider head reveal	PLY12	1500 x 40 x 12
K7-19	Slider head reveal	PLY12	1500 x 40 x 12
K7-05	Slider jamb reveal	PLY12	2240 x 40 x 12
K7-06	Slider jamb reveal	PLY12	2240 x 40 x 12
K7-07	Ceiling scribe strip over the over	PLY12	1600 x 16 x 12
K7-20	Galley end panel (scribed to the f	PLY12	862 x 600 x 12




PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Kit K7: Trims (exploded) **J-107**

Scale NTS · Rev A2 · 2026-10-28 · mm **PRELIMINARY**



Part	Name	Mat.	L x W x T
K11-01	Beam RHS 150x100x5, side 1	STEEL	6058 x 150 x 100
K11-02	Beam RHS 150x100x5, side 2	STEEL	6058 x 150 x 100
K11-03	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-04	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-05	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-06	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-07	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-08	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-09	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-10	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-11	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-12	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-13	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-14	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-15	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-16	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-17	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-18	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-19	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-20	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-21	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-22	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-23	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-24	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-25	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-26	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-27	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-28	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-29	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 102 x 25
K11-30	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-31	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-32	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-33	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-34	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-35	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-36	Guardrail top rail, hardwood 140 x	TIMBER	6058 x 50 x 40
K11-37	Guardrail cable infill, 4 mm stain	CABLE	6058 x 940 x 6
K11-38	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-39	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-40	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-41	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-42	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-43	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-44	Guardrail top rail, hardwood 140 x	TIMBER	6058 x 50 x 40
K11-45	Guardrail cable infill, 4 mm stain	CABLE	6058 x 940 x 6
K11-46	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-47	Guardrail top rail, hardwood 140 x	TIMBER	2438 x 50 x 40
K11-48	Guardrail cable infill, 4 mm stain	CABLE	2438 x 940 x 6
K11-49	Guardrail post SHS 50x50x3	STEEL	1060 x 50 x 50
K11-50	Guardrail top rail, hardwood 140 x	TIMBER	2438 x 50 x 40
K11-51	Guardrail cable infill, 4 mm stain	CABLE	2438 x 940 x 6
K11-52	Veranda post SHS 60x60x3 on the de	STEEL	2014 x 60 x 60
K11-53	Veranda post SHS 60x60x3 on the de	STEEL	2014 x 60 x 60
K11-54	Veranda post SHS 60x60x3 on the de	STEEL	2014 x 60 x 60
K11-55	Veranda ledger on its own posts	STEEL	6058 x 60 x 60
K11-56	Veranda polycarbonate 10 mm tinted	POLY	6058 x 1700 x 100
K11-57	Stair tread 1 (chequer plate on an	STEEL	850 x 250 x 40
K11-58	Stair tread 2 (chequer plate on an	STEEL	850 x 250 x 40
K11-59	Stair tread 3 (chequer plate on an	STEEL	850 x 250 x 40
K11-60	Stair tread 4 (chequer plate on an	STEEL	850 x 250 x 40


PRELIMINARY

Farm container studios farm.databayt.org/docs/studio


Kit K11: Roof terrace (exploded) **J-108**

Scale NTS · Rev A2 · 2026-10-28 · mm **PRELIMINARY**


MPLY18 sheet 1: 2440 x 1220, use 80 %




MPLY18 sheet 2: 2440 x 1220, use 80 %



MPLY18 sheet 3: 2440 x 1220, use 52 %




PLY12 sheet 1: 2440 x 1220, use 89 %



PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-101**
Scale 1:20 · Rev A2 · 2026-10-28 · mm	**PRELIMINARY**


PLY12 sheet 2: 2440 x 1220, use 88 %



PLY12 sheet 3: 2440 x 1220, use 88 %



PLY12 sheet 4: 2440 x 1220, use 88 %




PLY12 sheet 5: 2440 x 1220, use 88 %




PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	C-102
Scale 1:20 · Rev A2 · 2026-10-28 · mm	PRELIMINARY


PLY12 sheet 6: 2440 x 1220, use 92 %




PLY12 sheet 7: 2440 x 1220, use 92 %



PLY12 sheet 8: 2440 x 1220, use 91 %




PLY12 sheet 9: 2440 x 1220, use 91 %




PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	C-103
Scale 1:20 · Rev A2 · 2026-10-28 · mm	PRELIMINARY


PLY12 sheet 10: 2440 x 1220, use 91 %




PLY12 sheet 11: 2440 x 1220, use 88 %



PLY12 sheet 12: 2440 x 1220, use 92 %



PLY12 sheet 13: 2440 x 1220, use 87 %




PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-104**
Scale 1:20 · Rev A2 · 2026-10-28 · mm	**PRELIMINARY**


PLY12 sheet 14: 2440 x 1220, use 77 %




PLY12 sheet 15: 2440 x 1220, use 16 %



PLY18 sheet 1: 2440 x 1220, use 83 %




PLY18 sheet 2: 2440 x 1220, use 87 %




PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-105**
Scale 1:20 · Rev A2 · 2026-10-28 · mm	**PRELIMINARY**


PLY18 sheet 3: 2440 x 1220, use 87 %




PLY18 sheet 4: 2440 x 1220, use 86 %



PLY18 sheet 5: 2440 x 1220, use 87 %




PLY18 sheet 6: 2440 x 1220, use 83 %




PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-106**
Scale 1:20 · Rev A2 · 2026-10-28 · mm	**PRELIMINARY**


PLY18 sheet 7: 2440 x 1220, use 67 %



PLY18 sheet 8: 2440 x 1220, use 57 %



WTOP38 sheet 1: 3050 x 650, use 50 %



PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-107**
Scale 1:20 · Rev A2 · 2026-10-28 · mm	**PRELIMINARY**