Container studios: three identical farm-stay guest units

IKEA-style flat-pack fit-out of standard 20 ft containers · materials and fabrication in Kigali

Net interior 5798 x 2252 x 2323 mm (13.1 m2) · Layout A (D-015)
Bed up to 1,600 x 2,000 · kitchen 2170 mm run with induction and 80 L heater
Bathroom 1318 x 2252 mm · shower tray 1200 x 900
Max demand about 33 A per unit (heater/hob priority relay) · feeder 10 mm2
Shared septic 4.0 m3, 2 chambers 2:1 · storage tank 4.0 m3
Roof terrace on the corner castings · tinted polycarbonate canopies over the roof and front deck

Status: PRELIMINARY. Opening positions are photo estimates (+/-150 mm, AS-14).
Nothing is cut until study/studio/survey.csv is complete and the set is re-issued.
Structural items (roof terrace, canopies, stair) need an engineer's sign-off before guest use.
Electrical ratings are design intent until a RURA class A electrician designs and certifies.

No.	Title
A-001	Cover and drawing index
A-101	Existing condition (photo-scaled)
A-102	Layout options considered
A-103	Furniture and dimension plan
A-201	Interior elevations: back wall and front wall
A-202	End elevations and cross-section
A-401	Build-up details
S-101	Roof terrace, canopies and stair: plan and elevation
E-101	Electrical layout plan
E-201	Single-line diagram: site and unit board
E-202	Circuit schedule, earthing and bonding
P-101	Plumbing layout plan (supply and drainage)
P-201	Pipework isometric (unit)
P-301	Site water and sanitation schematic
J-101	Kit K1: Insulation and lining (exploded)
J-102	Kit K2: Bathroom (exploded)
J-103	Kit K3: Kitchen (exploded)
J-104	Kit K4: Bed (exploded)
J-105	Kit K5: Wardrobe (exploded)
J-106	Kit K6: Table and stools (exploded)
J-107	Kit K7: Trims (exploded)
J-108	Kit K11: Roof terrace (exploded)
C-101	Cutting diagrams (panel saw: rip strips, then crosscut)
C-102	Cutting diagrams (panel saw: rip strips, then crosscut)
C-103	Cutting diagrams (panel saw: rip strips, then crosscut)
C-104	Cutting diagrams (panel saw: rip strips, then crosscut)
C-105	Cutting diagrams (panel saw: rip strips, then crosscut)
C-106	Cutting diagrams (panel saw: rip strips, then crosscut)
C-107	Cutting diagrams (panel saw: rip strips, then crosscut)
C-108	Cutting diagrams (panel saw: rip strips, then crosscut)

PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Cover and drawing index **A-001**

Scale NTS · Rev A · 2026-10-26 · mm **PRELIMINARY**

PLAN (roof removed)




Existing (photo 2026-10-25, not published):
- standard 20 ft container on a raised steel deck, deck about 700 above ground, steps at end B
- sliding glass wall, white frames, about 3.0 x 2.25 m
- narrow hinged steel door near end B (about 0.55 m)
- yellow unit: original cargo doors at end B
- one corner casting rests on a rock: level first
- temporary wiring; timber lining in one unit

Positions are scaled from the 6,058 mm length [E]. Survey every unit before cutting (studio-site page).

Structure: the glazed side is about 60 % open and no longer braces the box (STU-03). Do not cut the back or end walls; holes there max 152 mm each.


FRONT ELEVATION (from the deck; end A on the left, as in the photo)



PRELIMINARY


Farm container studios	farm.databayt.org/docs/studio
Existing condition (photo-scaled)	**A-101**
Scale 1:30 · Rev A · 2026-10-26 · mm	PRELIMINARY

A (chosen): bath at the narrow-door end




PASS: robust to +/-150 mm; one wet core; door becomes a window

B: mirror (bath at end A)



Works, but the bathroom has no window and the bed sits by the steps

C: keep the narrow door as an entrance



FAIL: WC side 364 < 400, front 500 < 600; 550 mm door

Options checked by the generator against the same rules (scripts/studio/validate.py):
WC centreline at least 400 from walls and 600 clear in front; shower tray at least 1,000 x 900; kitchen aisle at least 900 to the glass; door and drawer sweeps clear of solids; partition on the solid strip after the glazing.
Layout A with the WC facing across the width passes at the photo estimate and at -150 / +150 mm (tests).
A first version with the WC facing along the container failed if the glazing ended more than about 70 mm later.
Precedents: Cleveland 20 ft (STU-46), Falcon (STU-47), Pod-Tainer (STU-48), container hotels (STU-49, STU-50).

PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Layout options considered	**A-102**
Scale 1:50 · Rev A · 2026-10-26 · mm	**PRELIMINARY**



Check	Rule	Result	Value
KO-WC	WC front clearance 600	pass	
KO-SHOWER	Shower entry 600	pass	
KO-BASIN	Standing space at the basin	pass	
KO-BDOOR	Bathroom door swing (opens outward, hinge at y 1,500)	pass	
KO-KITCHEN	Kitchen aisle 860 (worktop to the dining zone)	pass	
KO-DRAWERS	Drawer pull-out 700	pass	
KO-WARD	Wardrobe door swing	pass	
R-TRAY	Shower tray length (mm)	pass	1200 >= 1000
R-WC-SIDE	WC centreline to the end wall (mm)	pass	708 >= 400
R-WC-SIDE2	WC centreline to the partition (mm)	pass	610 >= 400
R-WC-FRONT	Clear space in front of the WC (mm)	pass	702 >= 600
R-AISLE	Kitchen aisle to the glass (mm)	pass	1632 >= 900
R-WARD	Wardrobe width (mm)	pass	600 >= 450
R-BED	Room beside the bed foot (mm)	pass	82 >= 50
R-HEIGHT	Clear height (mm)	pass	2323 >= 2250
R-PART	Partition clear of the old door (mm)	pass	510 >= 150


PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio


Furniture and dimension plan — **A-103**

Scale 1:25 · Rev A · 2026-10-26 · mm — PRELIMINARY

BACK WALL (looking at y = 0)



FRONT WALL (looking at the glass from inside; end B on the left)




PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Interior elevations: back wall and front wall — **A-201**

Scale 1:30 · Rev A · 2026-10-26 · mm — PRELIMINARY


END A (bed) looking at x = 0



SECTION AT THE KITCHEN looking to end A



END B (bathroom) looking at x = L




Clear height about 2,323 mm after a 60 mm ceiling and a 10 mm floor build-up (AS-15).
The 2012 rules asked 2.4 m over half a habitable room (STU-11, superseded); the founder reports approval.
Wall fans, not ceiling fans (blades would be below 2.1 m). Split-AC provision: sleeve + 16 A circuit.

PRELIMINARY


Farm container studios	farm.databayt.org/docs/studio
End elevations and cross-section	**A-202**
Scale 1:25 · Rev A · 2026-10-26 · mm	**PRELIMINARY**

WALL (steel to room)




steel | EPS | plywood | EPS | varnish

CEILING (roof to room)




EPS | plywood | EPS

BATHROOM WET WALL




stud | insulation | sheathing

PARTITION 70 (living | bath)



marine plywood | stud + insulation | plywood 12

FLOOR (living)



container plywood | EPS | deck

W1 (old door): 2 mm steel infill with 40 mm EPS welded into the existing frame up to 1,150; obscure louvre window above with insect mesh; the bathroom fan exits through the infill panel (no new hole in a bracing wall).

Floor: never sand the treated plywood (STU-07).
Drains pass between cross-members, never through them.
Steel faces: rust converter + zinc primer before foam.
All EPS joints foam-sealed: no air path to the steel.


PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio


Build-up details — **A-401**

Scale 1:5 · Rev A · 2026-10-26 · mm — PRELIMINARY

PLAN (canopies omitted)



FRONT ELEVATION



Element	Specification
Deck beams	RHS 150x100x5, 2 no., bear on the 4 corner castings only
Joists	RHS 80x40x3 at 600
Deck	hardwood boards 140 x 25, 5 mm gaps
Guardrail	1,100 high, mesh infill, gaps under 100
Upper canopy	tinted multiwall polycarbonate 10 mm, 5 deg, gutter
Veranda canopy	own posts + ledger over the front deck
Stair	dog-leg, 16 risers about 175, goings 250, 850 wide, handrails
Loads [A]	3.0 kN/m2 live, 0.74 kN/m rail, wind uplift: engineer to sign


The glazed side does not brace the box: nothing bears on the slider head or the open side's top rail (STU-03).
All steelwork bonded to the earth electrode (lightning).
Polycarbonate not found online in Kigali: fallback translucent GRP or opal corrugated sheet (Tolirwa / Safintra, field check).
Engineer's inspection before any guest uses the roof (R26).

PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Roof terrace, canopies and stair: plan and elevation — **S-101**

Scale 1:50 · Rev A · 2026-10-26 · mm — **PRELIMINARY**



Mounting heights z above the finished floor (mm). Sockets in the bathroom: none. Bathroom light IP65; extract fan in the W1 panel; switches outside the bathroom. Cables run in 20 mm conduit inside the batten cavity, in vertical drops and in horizontal zones at 300 and 1,100; grommets at every steel penetration. Outdoor points (deck, roof, stair) IP65/66 on the bonded steelwork.

S4/C1

L10/C1

Pt	Cct	Description	z
DB		Unit board on the partition	1625
L1	C1	Ceiling light, bed	2323
L2	C1	Ceiling light, living	2323
L3	C1	Ceiling light, kitchen	2323
L4	C1	Bathroom light IP65	2323
L5	C1	Reading light 1	1050
L6	C1	Reading light 2	1050
L7	C1	Under-cabinet LED strip	1440
L8	C1	Deck light IP65	2350
L9	C1	Roof terrace lights IP65 (x2)	2723
L10	C1	Stair light IP65	1500
S1	C1	Entry: living + kitchen + deck	1100
S2	C1	Bed: ceiling light (2-way)	900
S3	C1	Bathroom light + fan (outside)	1100
S4	C1	Roof and stair lights (IP65, stair foot)	1100
P1	C2	Bedside socket + USB-C 1	600
P2	C2	Bedside socket + USB-C 2	600
P3	C2	Socket by the bed (desk ledge)	300
P4	C2	Socket, living (front strip)	300
P5	C2	Deck socket IP66	400
P6	C3	Worktop socket 1 (double)	1100
P7	C3	Worktop socket 2 (double)	1100
P8	C3	Fridge socket	250
P9	C4	Hob connection unit	600


PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Electrical layout plan — **E-101**


Scale 1:25 · Rev A · 2026-10-26 · mm — **PRELIMINARY**

SITE



3-phase supply preferred, one studio per phase; otherwise single phase sized by REG.
Feeder 10 mm2 Cu SWA, 30 m [A], drop 1.9 % at max demand.
TT earthing: one earth rod per container; no PME to a steel structure unless certified (STU-37).

UNIT BOARD (identical in all three studios)



C4 hob and C5 heater share a priority relay: the heater pauses while the hob runs.
Diversified maximum demand about 33 A per unit (AS-19).
RCD type A on all circuits (or one RCBO per circuit). SPD type 2 at each unit.
Ratings are design intent: a RURA class A electrician designs and certifies (STU-15).
Wiring standard RS 565-1:2011 (STU-14); confirm every rating against it.

PRELIMINARY


Farm container studios	farm.databayt.org/docs/studio
Single-line diagram: site and unit board	E-201
Scale NTS · Rev A · 2026-10-26 · mm	PRELIMINARY

CIRCUIT SCHEDULE (Ib design current, Iz derated capacity, drop at the far point)

Cct	Serves	Device	mm2	Ib A	Iz A	Run m	Drop %
C1	Lighting (incl. bathroom IP65, deck, roo	B6	1.5	0.5	16.4	10.0	0.06
C2	Sockets: bedside USB, living, deck	B16	2.5	8.0	22.6	8.1	0.51
C3	Kitchen sockets and fridge	B16	2.5	13.5	22.6	6.1	0.64
C4	Induction hob	B20	4	15.2	30.1	5.1	0.37
C5	80 L water heater	B16	2.5	8.7	22.6	2.2	0.15
C6	Extract fan and wall fan	B6	1.5	0.3	16.4	4.8	0.02
C7	AC provision	B16	2.5	12.0	22.6	5.8	0.54
C8	Spare	B16	2.5	-	-	-	-

Maximum demand item	A
lighting	0.3
sockets	16.4
hob	11.6
heater	8.7
fans	0.3
ac	4.3
total_A	32.9

EARTHING AND BONDING (TT)




Bonding: finely stranded green-yellow (16 mm2 [A]) from each steel item to the MET. RA x 30 mA must stay under 50 V; aim much lower for lightning (measure on site). Tests before handover: continuity, insulation resistance, polarity, earth electrode resistance, RCD trip time, SPD status; certificate from the licensed electrician. Bathroom: zone 1 above the tray to 2.25 m (IPX4); 30 mA on every circuit (STU-38).

PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Circuit schedule, earthing and bonding | **E-202**

Scale NTS · Rev A · 2026-10-26 · mm | PRELIMINARY



Run	System	Size	m	Fall	Note
D1	soil	DN110	2.8	1:39	WC to IC1, 1:40
D2	waste	DN50	1.4	1:34	Shower (90 mm tray waste) joins the soil run
D3	waste	DN40	0.5	1:12	Basin joins the soil run
D4	waste	DN50	3.3	1:35	Kitchen sink to the grease trap (separate so
V1	vent	DN75	6.0	-	Open vent up end B to 900 above the guardrai
W1	cold	DN25	3.1	-	Cold main in: stop valve, filter, check mete
W2	cold	DN20	1.4	-	Cold feed to the heater
W3	cold	DN20	0.9	-	Cold to sink
W4	cold	DN20	3.0	-	Cold to WC cistern
W5	cold	DN20	1.1	-	Cold to basin
H1	hot	DN20	1.7	-	Hot (60 C) from the heater to the mixing val
H2	hot	DN20	0.6	-	Hot to sink (direct 60 C, labelled)
T1	tempered	DN20	1.7	-	TMV 41-44 C to the shower valve
T2	tempered	DN20	2.2	-	Tempered to basin


PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Plumbing layout plan (supply and drainage) — **P-101**


Scale 1:25 · Rev A · 2026-10-26 · mm — PRELIMINARY

Supply: PPR PN20, 20/25 mm. Hot leaves the 80 L heater at 60 C; a thermostatic mixer (TMV) delivers 41-44 C to the shower and basin; the kitchen sink gets direct hot (labelled).
Drainage hangs in the void under the raised floor (the container is about 700 mm up), between cross-members: WC 110, shower and sink 50, basin 40, falls at least 1:40.
Vent: 75 mm open vent up end B to 900 above the guardrail line (or an AAV inside).
Kitchen sink waste runs separately to a grease trap and its own soak pit (STU-11).



PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Pipework isometric (unit)	**P-201**
Scale NTS · Rev A · 2026-10-26 · mm	PRELIMINARY




Septic sizing, P = 8	m3
DRS 143 draft (STU-10)	4.0
2012 regulations (STU-11)	2.96
180P + 2,000 L (STU-09 style)	3.44
Design (largest, rounded)	4.0

Siting rules (check on the site plan):
- at least 50 m from the borehole and any well (2012 rules; DRS 143 draft: soak pit 18 m)
- at least 50 m from the lake (LOC-01, LOC-02)
- at least 3-7 m from buildings and the boundary
- downhill of the borehole; tanker within 30 m
- soak pit only where groundwater is more than 2.5 m down and percolation is 25-125 mm/h


No guests until the system passes inspection.

DRAINAGE



PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Site water and sanitation schematic	P-301
Scale NTS · Rev A · 2026-10-26 · mm	PRELIMINARY




Part	Name	Mat.	L x W x T
K1-01	Back wall lining	PLY12	2323 x 1102 x 12
K1-02	Back wall lining	PLY12	2323 x 1102 x 12
K1-03	Back wall lining	PLY12	2323 x 1102 x 12
K1-04	Back wall lining	PLY12	2323 x 1102 x 12
K1-05	End A lining	PLY12	2323 x 1126 x 12
K1-06	End A lining	PLY12	2323 x 1126 x 12
K1-07	Front wall lining (end A)	PLY12	2323 x 690 x 12
K1-08	Front wall lining (end A)	PLY12	2323 x 690 x 12
K1-09	Front head strip	PLY12	1500 x 83 x 12
K1-10	Front head strip	PLY12	1500 x 83 x 12
K1-11	Ceiling panel	PLY12	2252 x 1160 x 12
K1-12	Ceiling panel	PLY12	2252 x 1160 x 12
K1-13	Ceiling panel	PLY12	2252 x 1160 x 12
K1-14	Ceiling panel	PLY12	2252 x 1160 x 12
K1-15	Ceiling panel	PLY12	2252 x 1160 x 12

PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Kit K1: Insulation and lining (exploded) **J-101**

Scale NTS · Rev A · 2026-10-26 · mm **PRELIMINARY**




Part	Name	Mat.	L x W x T
K2-01	Partition skin (living face)	MPLY18	2323 x 750 x 18
K2-02	Partition skin (living face)	MPLY18	2323 x 750 x 18
K2-03	Partition skin over door	MPLY18	730 x 273 x 18
K2-04	Partition skin (front)	MPLY18	2323 x 22 x 18
K2-05	Door jamb (hinge side)	MPLY18	2050 x 70 x 18
K2-06	Door jamb (latch side)	MPLY18	2050 x 70 x 18
K2-07	Door head	MPLY18	694 x 70 x 18
K2-08	Mirror cabinet side 1	MPLY18	650 x 108 x 18
K2-09	Mirror cabinet side 2	MPLY18	650 x 108 x 18
K2-10	Mirror cabinet top	MPLY18	414 x 108 x 18
K2-11	Mirror cabinet bottom	MPLY18	414 x 108 x 18
K2-12	Mirror cabinet shelf	MPLY18	412 x 98 x 18
K2-13	Mirror cabinet door	MPLY18	650 x 450 x 18

PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Kit K2: Bathroom (exploded) **J-102**

Scale NTS · Rev A · 2026-10-26 · mm **PRELIMINARY**




Part	Name	Mat.	L x W x T
K3-01	Fridge bay side L	PLY18	762 x 588 x 18
K3-02	Fridge bay top rail	PLY18	582 x 100 x 18
K3-03	Fridge bay back rail	PLY18	582 x 100 x 18
K3-H-01	Hob base side L	PLY18	762 x 588 x 18
K3-H-02	Hob base side R	PLY18	762 x 588 x 18
K3-H-03	Hob base bottom	PLY18	588 x 414 x 18
K3-H-04	Hob base front rail	PLY18	414 x 100 x 18
K3-H-05	Hob base back rail	PLY18	414 x 100 x 18
K3-H-06	Hob base back	PLY12	762 x 450 x 12
K3-H-07	Hob base drawer front 1	PLY18	447 x 378 x 18
K3-H-08	Hob base drawer side L 1	PLY12	566 x 160 x 12
K3-H-09	Hob base drawer side R 1	PLY12	566 x 160 x 12
K3-H-10	Hob base drawer back 1	PLY12	364 x 160 x 12
K3-H-11	Hob base drawer bottom 1	PLY12	554 x 364 x 12
K3-H-12	Hob base drawer front 2	PLY18	447 x 378 x 18
K3-H-13	Hob base drawer side L 2	PLY12	566 x 160 x 12
K3-H-14	Hob base drawer side R 2	PLY12	566 x 160 x 12
K3-H-15	Hob base drawer back 2	PLY12	364 x 160 x 12
K3-H-16	Hob base drawer bottom 2	PLY12	554 x 364 x 12
K3-S-01	Sink base side L	PLY18	762 x 588 x 18
K3-S-02	Sink base side R	PLY18	762 x 588 x 18
K3-S-03	Sink base bottom	PLY18	588 x 564 x 18
K3-S-04	Sink base front rail	PLY18	564 x 100 x 18
K3-S-05	Sink base back rail	PLY18	564 x 100 x 18
K3-S-06	Sink base back	PLY12	762 x 600 x 12
K3-S-07	Sink base door 1	PLY18	758 x 297 x 18
K3-S-08	Sink base door 2	PLY18	758 x 297 x 18
K3-T-01	Tall unit side L	PLY18	2100 x 588 x 18
K3-T-02	Tall unit side R	PLY18	2100 x 588 x 18
K3-T-03	Tall unit bottom	PLY18	588 x 484 x 18
K3-T-04	Tall unit top	PLY18	588 x 484 x 18
K3-T-05	Tall unit back	PLY12	2100 x 520 x 12
K3-T-06	Tall unit shelf 1	PLY18	566 x 482 x 18
K3-T-07	Tall unit shelf 2	PLY18	566 x 482 x 18
K3-T-08	Tall unit door 1	PLY18	2096 x 257 x 18
K3-T-09	Tall unit door 2	PLY18	2096 x 257 x 18
K3-WT	Worktop 38 mm	WTOP38	1650 x 620 x 38
K3-W1-01	Wall unit 1 side L	PLY18	700 x 308 x 18
K3-W1-02	Wall unit 1 side R	PLY18	700 x 308 x 18
K3-W1-03	Wall unit 1 bottom	PLY18	564 x 308 x 18
K3-W1-04	Wall unit 1 top	PLY18	564 x 308 x 18
K3-W1-05	Wall unit 1 back	PLY12	700 x 600 x 12
K3-W1-06	Wall unit 1 shelf 1	PLY18	562 x 286 x 18
K3-W1-07	Wall unit 1 door 1	PLY18	696 x 597 x 18
K3-W2-01	Wall unit 2 side L	PLY18	700 x 308 x 18
K3-W2-02	Wall unit 2 side R	PLY18	700 x 308 x 18
K3-W2-03	Wall unit 2 bottom	PLY18	564 x 308 x 18
K3-W2-04	Wall unit 2 top	PLY18	564 x 308 x 18
K3-W2-05	Wall unit 2 back	PLY12	700 x 600 x 12
K3-W2-06	Wall unit 2 shelf 1	PLY18	562 x 286 x 18
K3-W2-07	Wall unit 2 door 1	PLY18	696 x 597 x 18
K3-HS	Shelf over the hob (hood mount)	PLY18	450 x 320 x 18
K3-PL	Plinth	PLY18	2170 x 98 x 18

PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Kit K3: Kitchen (exploded) — **J-103**

Scale NTS · Rev A · 2026-10-26 · mm — **PRELIMINARY**




Part	Name	Mat.	L x W x T
K4-01	Rail, end-A side	PLY18	2020 x 432 x 18
K4-02	Rail, room side (top)	PLY18	2020 x 80 x 18
K4-03	Rail, room side (plinth)	PLY18	2020 x 60 x 18
K4-04	Rail, head	PLY18	1604 x 432 x 18
K4-05	Rail, foot	PLY18	1604 x 432 x 18
K4-06	Spine (drawer back)	PLY18	1984 x 432 x 18
K4-07	Drawer divider at y 650	PLY18	682 x 352 x 18
K4-08	Drawer divider at y 1400	PLY18	682 x 352 x 18
K4-09	Deck panel 1 (ventilated)	PLY18	2020 x 802 x 18
K4-10	Deck panel 2 (ventilated)	PLY18	2020 x 802 x 18
K4-11	Suitcase flap (lift-up, gas strut)	PLY18	473 x 292 x 18
K4-12	Drawer 1 front	PLY18	732 x 288 x 18
K4-13	Drawer 1 side 1	PLY12	662 x 230 x 12
K4-14	Drawer 1 side 2	PLY12	662 x 230 x 12
K4-15	Drawer 1 back	PLY12	688 x 230 x 12
K4-16	Drawer 1 bottom	PLY12	688 x 650 x 12
K4-17	Drawer 2 front	PLY18	743 x 288 x 18
K4-18	Drawer 2 side 1	PLY12	662 x 230 x 12
K4-19	Drawer 2 side 2	PLY12	662 x 230 x 12
K4-20	Drawer 2 back	PLY12	699 x 230 x 12
K4-21	Drawer 2 bottom	PLY12	699 x 650 x 12
K4-22	Headboard front	PLY18	1640 x 650 x 18
K4-23	Headboard shelf	PLY18	1640 x 150 x 18
K4-24	Headboard end	PLY18	632 x 132 x 18

PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Kit K4: Bed (exploded) **J-104**

Scale NTS · Rev A · 2026-10-26 · mm **PRELIMINARY**



Part	Name	Mat.	L x W x T
K5-01	Wardrobe side L	PLY18	2100 x 588 x 18
K5-02	Wardrobe side R	PLY18	2100 x 588 x 18
K5-03	Wardrobe bottom	PLY18	588 x 564 x 18
K5-04	Wardrobe top	PLY18	588 x 564 x 18
K5-05	Wardrobe back	PLY12	2100 x 600 x 12
K5-06	Wardrobe shelf 1	PLY18	566 x 562 x 18
K5-07	Wardrobe door 1	PLY18	2096 x 597 x 18


PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio

Kit K5: Wardrobe (exploded) — **J-105**

Scale NTS · Rev A · 2026-10-26 · mm — PRELIMINARY

Part	Name	Mat.	L x W x T
K6-01	Table top 600 x 600	PLY18	600 x 600 x 18
K6-02	Table leg A (cross-halving slot)	PLY18	732 x 500 x 18
K6-03	Table leg B (cross-halving slot)	PLY18	732 x 500 x 18
K6-04	Stool 1 seat	PLY18	320 x 320 x 18
K6-05	Stool 1 leg A	PLY18	432 x 280 x 18
K6-06	Stool 1 leg B	PLY18	432 x 280 x 18
K6-07	Stool 2 seat	PLY18	320 x 320 x 18
K6-08	Stool 2 leg A	PLY18	432 x 280 x 18
K6-09	Stool 2 leg B	PLY18	432 x 280 x 18




PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Kit K6: Table and stools (exploded) **J-106**

Scale NTS · Rev A · 2026-10-26 · mm **PRELIMINARY**

Part	Name	Mat.	L x W x T
K7-03	Skirting, front strip	PLY12	1368 x 70 x 12
K7-04	Slider head reveal	PLY12	1500 x 40 x 12
K7-19	Slider head reveal	PLY12	1500 x 40 x 12
K7-05	Slider jamb reveal	PLY12	2240 x 40 x 12
K7-06	Slider jamb reveal	PLY12	2240 x 40 x 12
K7-07	Ceiling scribe strip (back)	PLY12	520 x 40 x 12
K7-20	Scribe strip 40 (per-unit fillers,	PLY12	2200 x 12 x 0




PRELIMINARY

Farm container studios farm.databayt.org/docs/studio

Kit K7: Trims (exploded) **J-107**

Scale NTS · Rev A · 2026-10-26 · mm **PRELIMINARY**



Part	Name	Mat.	L x W x T
K11-01	Beam RHS 150x100x5, side 1	STEEL	6058 x 150 x 100
K11-02	Beam RHS 150x100x5, side 2	STEEL	6058 x 150 x 100
K11-03	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-04	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-05	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-06	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-07	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-08	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-09	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-10	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-11	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-12	Joist RHS 80x40x3	STEEL	2238 x 80 x 40
K11-13	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-14	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-15	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-16	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-17	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-18	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-19	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-20	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-21	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-22	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-23	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-24	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-25	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-26	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-27	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-28	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 140 x 25
K11-29	Deck board 140 x 25 hardwood (trea	TIMBER	6058 x 102 x 25
K11-30	Guardrail top rail SHS 40x40x3	STEEL	6058 x 40 x 40
K11-31	Guardrail mesh panel (gaps under 1	MESH	6058 x 960 x 40
K11-32	Guardrail top rail SHS 40x40x3	STEEL	6058 x 40 x 40
K11-33	Guardrail mesh panel (gaps under 1	MESH	6058 x 960 x 40
K11-34	Guardrail top rail SHS 40x40x3	STEEL	2438 x 40 x 40
K11-35	Guardrail mesh panel (gaps under 1	MESH	2438 x 960 x 40
K11-36	Guardrail top rail SHS 40x40x3	STEEL	2438 x 40 x 40
K11-37	Guardrail mesh panel (gaps under 1	MESH	2438 x 960 x 40
K11-38	Canopy post SHS 80x80x4	STEEL	2400 x 80 x 80
K11-39	Canopy post SHS 80x80x4	STEEL	2620 x 80 x 80
K11-40	Canopy post SHS 80x80x4	STEEL	2400 x 80 x 80
K11-41	Canopy post SHS 80x80x4	STEEL	2620 x 80 x 80
K11-42	Upper canopy polycarbonate 10 mm t	POLY	6658 x 3038 x 230
K11-43	Veranda post SHS 60x60x3 on the de	STEEL	2021 x 60 x 60
K11-44	Veranda post SHS 60x60x3 on the de	STEEL	2021 x 60 x 60
K11-45	Veranda post SHS 60x60x3 on the de	STEEL	2021 x 60 x 60
K11-46	Veranda ledger on its own posts	STEEL	6058 x 60 x 60
K11-47	Veranda polycarbonate 10 mm tinted	POLY	6058 x 1700 x 100
K11-48	Stair tread 1 (chequer plate on an	STEEL	850 x 250 x 40
K11-49	Stair tread 2 (chequer plate on an	STEEL	850 x 250 x 40
K11-50	Stair tread 3 (chequer plate on an	STEEL	850 x 250 x 40
K11-51	Stair tread 4 (chequer plate on an	STEEL	850 x 250 x 40
K11-52	Stair tread 5 (chequer plate on an	STEEL	850 x 250 x 40
K11-53	Stair tread 6 (chequer plate on an	STEEL	850 x 250 x 40
K11-54	Stair tread 7 (chequer plate on an	STEEL	850 x 250 x 40
K11-55	Stair tread 8 (chequer plate on an	STEEL	850 x 250 x 40
K11-56	Stair tread 9 (chequer plate on an	STEEL	850 x 250 x 40
K11-57	Stair tread 10 (chequer plate on a	STEEL	850 x 250 x 40
K11-58	Stair tread 11 (chequer plate on a	STEEL	850 x 250 x 40
K11-59	Stair tread 12 (chequer plate on a	STEEL	850 x 250 x 40
K11-60	Stair tread 13 (chequer plate on a	STEEL	850 x 250 x 40


PRELIMINARY

Farm container studios — farm.databayt.org/docs/studio


Kit K11: Roof terrace (exploded) — **J-108**

Scale NTS · Rev A · 2026-10-26 · mm — **PRELIMINARY**


MPLY18 sheet 1: 2440 x 1220, use 78 %



MPLY18 sheet 2: 2440 x 1220, use 68 %



MPLY18 sheet 3: 2440 x 1220, use 10 %




PLY12 sheet 1: 2440 x 1220, use 89 %



PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-101**
Scale 1:20 · Rev A · 2026-10-26 · mm	**PRELIMINARY**


PLY12 sheet 2: 2440 x 1220, use 88 %



PLY12 sheet 3: 2440 x 1220, use 88 %



PLY12 sheet 4: 2440 x 1220, use 88 %




PLY12 sheet 5: 2440 x 1220, use 88 %




PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-102**
Scale 1:20 · Rev A · 2026-10-26 · mm	**PRELIMINARY**


PLY12 sheet 6: 2440 x 1220, use 92 %




PLY12 sheet 7: 2440 x 1220, use 91 %



PLY12 sheet 8: 2440 x 1220, use 90 %




PLY12 sheet 9: 2440 x 1220, use 90 %




PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-103**
Scale 1:20 · Rev A · 2026-10-26 · mm	**PRELIMINARY**


PLY12 sheet 10: 2440 x 1220, use 91 %




PLY12 sheet 11: 2440 x 1220, use 88 %



PLY12 sheet 12: 2440 x 1220, use 81 %




PLY12 sheet 13: 2440 x 1220, use 87 %




PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-104**
Scale 1:20 · Rev A · 2026-10-26 · mm	**PRELIMINARY**


PLY12 sheet 14: 2440 x 1220, use 82 %




PLY12 sheet 15: 2440 x 1220, use 54 %



PLY12 sheet 16: 2440 x 1220, use 28 %




PLY18 sheet 1: 2440 x 1220, use 85 %



PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-105**
Scale 1:20 · Rev A · 2026-10-26 · mm	**PRELIMINARY**


PLY18 sheet 2: 2440 x 1220, use 86 %




PLY18 sheet 3: 2440 x 1220, use 82 %



PLY18 sheet 4: 2440 x 1220, use 85 %



PLY18 sheet 5: 2440 x 1220, use 83 %




PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-106**
Scale 1:20 · Rev A · 2026-10-26 · mm	**PRELIMINARY**

PLY18 sheet 6: 2440 x 1220, use 83 %



PLY18 sheet 7: 2440 x 1220, use 87 %



PLY18 sheet 8: 2440 x 1220, use 82 %



PLY18 sheet 9: 2440 x 1220, use 87 %




PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-107**
Scale 1:20 · Rev A · 2026-10-26 · mm	**PRELIMINARY**


PLY18 sheet 10: 2440 x 1220, use 87 %



PLY18 sheet 11: 2440 x 1220, use 68 %



WTOP38 sheet 1: 3050 x 650, use 52 %



PRELIMINARY

Farm container studios	farm.databayt.org/docs/studio
Cutting diagrams (panel saw: rip strips, then crosscut)	**C-108**
Scale 1:20 · Rev A · 2026-10-26 · mm	**PRELIMINARY**